
74 S 09 Quad 2-Input AND Gates with Open-Collector Outputs

Y = AB





Atari, inc. 30 E. Plumaria Drive San Jose, CA 95134


W A Warner Communications Company

SIZE DRA

DRAWING NO. CO25671 - 001 rev | A

SCALE

SHEET 6 OF 6



Parallel Bus Expansion Memory
Specifications

Steve Miller

11/17/83

C024891-001

ATARI COMPANY CONFIDENTIAL

		DRAWN BY DATE		人	_	Atari 0 E. Plun ian Jose,	naria	Driv	
NEXT ASSY USED ON NOTICE TO ALL PERSONS RECEIVING THIS DRAWING CONFIDENTIAL: Reproduction Forbidden without the specific written permission of Atarl Inc., Sunnyvale, California. This drawing is only conditionally issued, and neither receipt nor		CHECKED		ATARI" •		A Warner Communications Company			
		ENGINEER Steve Mille	тпе	Paralle Memory	el Bu Spec	ıs Expa	ansi ior	lon is	
possession thereof confers or tranuse, the subject matter of the draw information shown thereon, no	wing or any design or technical	APPROVED							
drawing or any part thereof, exci for Atari Incorporated and for m tion's written license, no right it	ept for manufacture by vendors anufacture under the corpora- to reproduce this drawing is	APPROVED	SIZE	DRAWING N		1-001			REV
granted or the subject matter the ment with or written permission	ereof unless by written agree-		SCALE			SHEET	1	OF	10

1.0 Introduction

This document defines the 48K Memory Expansion Card for the 600XL computer. It will allow the user to expand their computer to a full 64K of RAM making it have the capability of the 800XL computer.

1.1 References

P.B.I. Specfication C061902 S. Miller Sweet 16 Product Spec C061186 A. Chopra

2.0 Consumer Profile

The typical user will be the first time computer user who, after a small inital investement in a computer, will want to expand into a larger system without an additional expense of buying a second computer system. Using this option we now have a path for a person to grow with his "starter system" to a advance home computer system. This expansion card gives the capability of the existing 800XL. Further addition of the Expansion Box will allow upgrages to a advanced tool for modern times.

3.0 Mechanical Design

The Parallel Bus Memory Expansion should have the XL-series styling and fit in back of the 600XL computer flush with the table top. The unit will also include room for a RFI sheild.

3.1 Dimensions

Lenght 7.31 inches
Depth 4.19 inches
Height 1.63 inches

Weight 2.5 lbs.



Atari, Inc. 30 E. Plumaria Drive San Jose, CA 95134

Marker Communication on Instant

SIZE	drawing no.	DRAWING NO.				
A	C024891	C024891-001				
SCALE		SHEET	2	OF	: 10	

4.0 <u>Electrical Design</u>

The Memory Expansion should contain enough memory to allow expansion of the 600%L to 64K. It should also meet the timing requirements of the P.B.I. In addition, it will also provide an interface to the Expansion Box in the rear of the unit. The interface will contain all the signals of the P.B.I. except reserved and power (+5VDC).

Power for the unit will be supplied by the $600\mathrm{XL}$ computer. This includes all interface logic and the RAM.

Shown in Figure 1 are the signals used in the Memory Expansion Device. A brief description follows. Not all the signals are used for the expansion ram but are included for completeness.

t m f
124
/8%
人
ATARI
ΔΙΔΙΚΙ


Atari, Inc. 30 E. Plumaria Drive San Jose, CA 95134

C A Marrier		4 m je		,	1000
-------------	--	--------	--	---	------

SIZE A	drawing no. C024891-0	001		REV
SCALE		sнеет 3	OF	10

	Parallel	Bus	Expansion	Memory	Specficat	ion	Rev 2	A
		GND	j., 1		2	EXTS	SEL'	
		АØ	3		4	Al		
		A2	5		6	АЗ		
		A4	7		8	A5		
		A6	. 9	:	LØ	GND		
		A7	• 11	:	1.2	A8		
		A9	13		14	Alø		
		All	15		16	A12		
		A13	17		18	A14		
		GND	19		2Ø	A15		
	Rese	DØ	21		22	Dl		
		D2	23		24	D3		
		D4	25		26	D5		
		D6	27		28	ס7		CONSOLE
CONSOLE TOP		GND	29		3Ø	GNE)	BOTTOM
		вø2	31		32	GNE)	
		erved	33		34	RST		
		IRQ	' 35		36	RDY	7	
	Rese	erved	37		38	EXT	TENB	
	Rese	erved	39		4ø	REF	, ,	
		CAS	41		42	GNI)	
		MPD	43		44	RAS	5'	
		GND	45		46	LR,	/w'	
	Res	erved	47		48	Res	served	t
		AUE	10 49		5Ø	GNI	D	

Figure 1 PBI Connector (Looking out of the Computer from the Inside)



4.1 Signals

Shown in figure 1 is the pin-out of the connector looking out of the computer. The signal names and functions are described below.

410 400-	_	
Pin 2	EXTSEL'	External Select (Input) ==> This open collector line is generated internally by the Parallel Bus Device (PBD). This signal should be active low whenever EXTENB is active and the PBD is selected and there is a valid PBD address on the bus. EXSEL' causes a CAS' inhibit on the main board allowing a remapping process. Although PBD can be mapped in any VALID RAM location, these devices should follow the ATARI guidelines for PBD locations so future ATARI devices can be used. The drive device should be capable of sinking 5 mA.
Pin 3	AØ	Address Line \emptyset (Output) ==> Address line \emptyset is a unbuffered output from the microprocessor.
Pin 4	Al	Address Line 1 (Output) ==> Address line 1 is a unbuffered output from the microprocessor.
Pin 5	A2	Address Line 2 (Output) ==> Address line 2 is a unbuffered output from the microprocessor.
Pin 6	A3	Address Line 3 (Output) ==> Address line 3 is a unbuffered output from the microprocessor.
Pin 7	A4	Address Line 4 (Output) ==> Address line 4 is a unbuffered output from the microprocessor.
Pin 8	A5	Address Line 5 (Output) ==> Address line 5 is a unbuffered output from the microprocessor.
Pin 9	А6	Address Line 6 (Output) ==> Address line 6 is a unbuffered output from the microprocessor.
Pin 11	A7	Address Line 7 (Output) ==> Address line 7 is a unbuffered output from the microprocessor.

A	Atari, Inc. 30 E. Plumaria Drive	SIZE A	DRAWING NO. C024891	REV	
ATARI"	San Jose, CA 95134	SCALE		SHEET 5	OF 10

	Parallel	Bus Expans	sion Memory Specfication Rev 2A
	Pin 12	A8	Address Line 8 (Output) ==> Address line 8 is a unbuffered output from the microprocessor.
Ē	Pin 13	A9	Address Line 9 (Output) ==> Address line 9 is a unbuffered output from the microprocessor.
E	Pin 14	Alø	Address Line 10 (Output) ==> Address line 10 is a unbuffered output from the microprocessor.
]	Pin 15	A11	Address Line 11 (Output) ==> Address line 11 is a unbuffered output from the microprocessor.
	Pin 16	A12	Address Line 12 (Output) ==> Address line 12 is a unbuffered output from the microprocessor.
	Pin 17	A13	Address Line 13 (Output) ==> Address line 13 is a unbuffered output from the microprocessor.
	Pin 18	A14	Address Line 14 (Output) ==> Address line 14 is a unbuffered output from the microprocessor.
	Pin 20	A15	Address Line 15 (Output) ==> Address line 15 is a unbuffered output from the microprocessor.
	Pin 21	DØ	Data Line \emptyset (Bi-directional) ==> Data line \emptyset is a buffered line in the 12XX models and unbuffered in the 6 \emptyset \emptyset and 8 \emptyset \emptyset computers.
	Din 22	D1	Data Line 1 (Bi-directional) ==> Data

Pin 22	Dl	Data Line 1 (Bi-directional) == Data line 1 is a buffered line in the 12XX models and unbuffered in the 600 and 800 computers.
Pin 23	D2	Data Line 2 (Bi-directional) ==> Data line 2 is a buffered line in the 12XX models and unbuffered in the 600 and 800 computers.
5: 24	D.3	Data Line 3 (Bi-directional) ==> Data

Pin 24 D3 Data Line 3 (Bi-directional) line 3 is a buffered line in models and unbuffered in the computers.	n the 12XX
---	------------

SCALE

八	
ATARI'	

Atari, Inc. 30 E. Plumaria Drive San Jose, CA 95134

© 4 warrier 1 mm and are risk in imparts

SIZE	DRAWING NO.
Α	C024891-001

SHEET 6 OF 10

REV

Pin 25	D 4	Data Line 4 (Bi-directional) ==> Data line 4 is a buffered line in the 12XX models and unbuffered in the 600 and 800 computers.
Pin 26	D5	Data Line 5 (Bi-directional) ==> Data line 5 is a buffered line in the 12XX models and unbuffered in the 600 and 800 computers.
Pin 27	D6	Data Line 6 (Bi-directional) $==>$ Data line 6 is a buffered line in the 12XX models and unbuffered in the 600 and 800 computers.
Pin 28	D7	Data Line 7 (Bi-directional) ==> Data line 7 is a buffered line in the 12XX models and unbuffered in the 600 and 800 computers.
Pin 31	вø2	Buffered Phase 2 Clock (Output) ==> This clock output line is a buffered phase 2 clock from the processor.
Pin 34	RST'	Reset (Output) ==> Reset is a active low signal which occurs either on power-up or by depressing the reset key.
Pin 35	IRQ'	Interrupt Request (Input) ==> This open collector line creates a interrupt on the microprocessor. The interrupt can then invoke the handler ROM or other service routines for the PBD. The driving device should be capable of sinking 5 mA.
Pin 36	RDY	Ready (Input) ==> This open collector input signal allows the PBD to halt the microprocessor ONLY during read cycles. This will extend the read cycle for slow peripherals. The driving device should be capable of sinking 5 mA.
Pin 38	EXTENB	External Decoder Enable (Output) ==> This output goes high when there is a valid RAM access. Any PBD can map during a valid EXTENB but the PBD should only map in according to ATARI specified address locations.

八
ATARI

Atari, Inc. 30 E. Plumaria Drive San Jose, CA 95134

CA warrier 1 mm unilater i ilin holi v

SIZE A	drawing no. C024891+0	001		REV
SCALE		SHEET 7	OF	: 10

REV

Pin	4ø	REF'	Refresh (Output) ==>This output can be for refresh timing on voltile memories connected to the PBI.
Pin	41	CAS'	Column Address Strobe (Output) ==> This output can be used for access of DRAM external to the computer. Due to timing restrictions caution should be taken when using this signal in the expansion box.
Pin	43	MPD'	Math Pack Disable (Input) ==> This open collector input is used to disable the math pack section of the OS ROM (D8ØØH-DFFFH). This should be done when the PBD is selected and has a handler resident. The driving device should be capable of sinking 5 mA.
Pin	44	RAS'	Row Address Strobe (Output) ==> This output can be used for access of DRAM external to the computer. Due to timing restrictions caution should be taken when using this signal in the expansion box.
Pin	46	LRØW'	Latched Read Write (Output) ==> This output is active high for a read cycle and active low for a write cycle.
Pin	49	AUDIO	Audio In (Input) ==> This line is tied directly to the audio summation network of the computer. The audio signal input is 100 mV peak to peak with 4.7K ohm source impedance.

Pins 1,10,19,29,30,32,42,45,50 GND

Pins 47,48 +5 VDC

Pins 33,37,39 Reserved

191
ATARI"
CALCAINI

Atari, Inc. 30 E. Plumaria Drive San Jose, CA 95134

SIZE A	drawing no. C024891-0	001			REV 1
SCALE		SHEET	8	OF	10

Product Performance 5.0

This section will specify the projected performance of the Memory Expansion. The environmental and reliablity information is included is targeted from the sweet 16 sepecfication.

Enviromental 5.1

Operating Environment

Temperature =

45 degrees C Maximum: 10 degrees C Minimum:

Humidity =

90% R.H. (Non Condensing) Maximum:

15% R.H. Minimum:

Altitude =

3000 Meters (9840 feet) (720 millibars) Maximum: -60 Meters (-197 feet) below sea level Minimum:

Non-Operating Environment

Temperature =

60 degrees C Maximum: 30 degrees C Minimum:

Humidity =

90% R.H. Should condensing occur unit Maximum: 0% R.H. must be dried off before Minimum:

operation

Altitude = Same as operating

Endurance Levels 5.2

ESD Susceptiablity

No product damage or data loss with 10KV to 20KV discharge at any point accessible to the user except the connectors with 65% RH.

Vibration

Operation:

.1g + 10% 5 to 500Hz Sine scan 5-100 Hz dwell on resonances Resonance Search:

1.0g for 10 minutes.



Atari, Inc. 30 E. Plumaria Drive San Jose, CA 95134

Calculation of the second of t

,		
ļ		

DRAWING NO. SIZE C024891-001 Α

REV

SCALE

of 10 SHEET 9

100 to 300 cycles per minute 2 directions Transportation:

90 degrees apart, 30 minutes; each frequency to be such as to raise package from the table 0.06 in., acceleration to be 1.0g (min) No Damage should result.

Impact Test:

Free fall distance of 24 in. on corner, edge, and all 6 faces. No damage should

occur to a packed unit.

Ramdom Vibration:

0.04g 2Hz 15minutes; 10 to 1000Hz 6.3g

RMS

Termal Shock:

10 degrees C for 3 hours power on raise temperature, 5 degrees per minute to 45 degrees C for 5 hours power off drop temperature 5 degrees C per minute to 10 degrees C. Repeat cycle 5 times no

damage.

5.3 MTBF & MTTR

The targeted MTBF for the Memory Expansion is 8000 hours continous power-on at 25 degrees C.

The targeted MTTR for the unit is 5 minutes.

5.4 Compliances

UL 114 & UL 94HB CSA C22.2 No. 154

FCC Docket 20780, Part 15, Subpart J, Class B

_		
	八	
	ATARI	

Atari, Inc. 30 E. Plumaria Drive San Jose, CA 95134

🕶 4 Agmer 3 in myr Lations tumbary

DRAWING NO. SIZE C024891-001 Α

REV